

WECK LABORATORIES, INC.

Certificate of Analysis

FINAL REPORT

Work Orders: 7F13088 **Report Date:** 6/30/2017

Received Date: 6/13/2017

Project: Carlsbad Desal Plant - WEEKLY

Turnaround Time: Normal

Phones: 1(619) 487-0760

Fax:

P.O. #:

Billing Code:

Attn: Peter Shen

Client: IDE Americas, Inc. - Carlsbad CA

4590 Carlsbad Blvd Carlsbad, CA 92008

DoD-ELAP #L2457 • ELAP-CA #1132 • EPA-UCMR #CA00211 • Guam-EPA #17-008R • HW-DOH # • ISO 17025 #L2457.01 • LACSD #10143 • NELAP-CA #04229CA • NELAP-OR #4047 • NV-DEP #NAC 445A • SCAQMD #93LA1006

This is a complete final report. The information in this report applies to the samples analyzed in accordance with the chain-of-custody document. Weck Laboratories certifies that the test results meet all requirements of TNI unless noted by qualifiers or written in the Case Narrative. This analytical report must be reproduced in its entirety.

Dear Peter Shen,

Enclosed are the results of analyses for samples received 6/13/17 with the Chain-of-Custody document. The samples were received in good condition, at 2.9 °C and on ice. All analyses met the method criteria except as noted in the case narrative or in the report with data qualifiers.

Reviewed by:

Kim G. Tu Project Manager














FINAL REPORT

WECK LABORATORIES, INC.

IDE Americas, Inc. - Carlsbad CA

Project Number: Carlsbad Desal Plant - WEEKLY

Reported: 06/30/2017 13:05

4590 Carlsbad Blvd Carlsbad, CA 92008

Project Manager: Peter Shen

XX


Sample Summary

Sample Name	Sampled By	Lab ID	Matrix	Sampled	Qualifiers
M-001 (17-2004)	Kevin Curry	7F13088-01	Water	06/09/17 08:15	
M-INF (17-2003)	Kevin Curry	7F13088-02	Water	06/09/17 04:05	
M-002 (17-2002)	Kevin Curry	7F13088-03	Water	06/09/17 04:02	

XX

Not Certified Analyses Summary

Analyte	CAS#	Not Accredited By
SM 2520B in Water		
Salinity		NELAP



FINAL REPORT

WECK LABORATORIES, INC.

IDE Americas, Inc. - Carlsbad CA 4590 Carlsbad Blvd Carlsbad, CA 92008 Project Number: Carlsbad Desal Plant - WEEKLY

Reported:

06/30/2017 13:05

N	Λ	M	
1			•

Sample Results

Sample:	M-001 (17-2004) 7F13088-01 (Water)					Sampled: 0	6/09/17 8:15 by Ke	vin Curry
Analyte Conventional C	hemistry/Physical Parameters by APHA/EPA/ASTM Methods	Result	MDL	MRL	Units	Dil	Analyzed	Qualifier

Project Manager: Peter Shen

Analyte	Result	MDL	MRL	Units	Dil	Analyzed	Qualifier
Conventional Chemistry/Physic	al Parameters by APHA/EPA/ASTM Methods						
Method: EPA 1664B	Batch ID: W7F1189		Prepared: 06/2	1/17 08:48			Analyst: joh
Oil & Grease (HEM)	1.6	1.3	5.0	mg/l	1	06/21/17 17:08	J
Method: SM 2520B	Batch ID: W7F1124		Prepared: 06/2	0/17 12:11			Analyst: stg
Salinity	56		•	ppt	1	06/20/17 16:34	
Method: SM 2540D	Batch ID: W7F0859		Prepared: 06/1	5/17 13:17			Analyst: ajk
Total Suspended Solids			5	mg/l	1	06/15/17 16:05	



FINAL REPORT

WECK LABORATORIES, INC. IDE Americas, Inc. - Carlsbad CA

4590 Carlsbad Blvd

Project Number: Carlsbad Desal Plant - WEEKLY

Reported:

(Continued)

Qualifier

06/30/2017 13:05

Carlsbad, CA 92008

Project Manager: Peter Shen

Sample Results Sample: M-INF (17-2003)

7F13088-02 (Water)

Sampled: 06/09/17 4:05 by Kevin Curry

Analyzed

Analyte

Conventional Chemistry/Physical Parameters by APHA/EPA/ASTM Methods

MDL

MRL

Units

Dil

Result

Method: SM 2520B Batch ID: W7F1124 Prepared: 06/20/17 12:11 Analyst: stg 06/20/17 16:34 Salinity ppt

7F13088 Page 4 of 8



FINAL REPORT

WECK LABORATORIES, INC.

IDE Americas, Inc. - Carlsbad CA 4590 Carlsbad Blvd Carlsbad, CA 92008

Project Number: Carlsbad Desal Plant - WEEKLY

Reported:

06/30/2017 13:05

Analyte

Sample Results

(Continued)

Qualifier

Sampled: 06/09/17 4:02 by Kevin Curry

Analyzed

Sample: M-002 (17-2002)

> 7F13088-03 (Water) MDL

MRL

Units

Dil


Conventional Chemistry/Physical Parameters by APHA/EPA/ASTM Methods

Method: SM 2520B Batch ID: W7F1124 Prepared: 06/20/17 12:11 Analyst: stg

Result

Project Manager: Peter Shen

06/20/17 16:34 Salinity ppt



FINAL REPORT

WECK LABORATORIES, INC.

IDE Americas, Inc. - Carlsbad CA 4590 Carlsbad Blvd Carlsbad, CA 92008 Project Number: Carlsbad Desal Plant - WEEKLY

Project Manager: Peter Shen

Reported:

06/30/2017 13:05



Quality Control Results

·								
Conventional Chemistry/Physical Parameters	by APHA/EPA/ASTM Methods							
			Spike	Source	%REC		RPD	
Analyte	Result MDL	Units	Level	Result %REC	Limits	RPD	Limit	Qualifier
Batch: W7F0859 - SM 2540D								
Blank (W7F0859-BLK1)			Prepared & A	nalyzed: 06/15/17				
Total Suspended Solids	· · · · · · · · · · · · · · · ND	mg/l						
LCS (W7F0859-BS1)			•	nalyzed: 06/15/17				
Total Suspended Solids	65.0	mg/l	59.3	110	90-110			
Duplicate (W7F0859-DUP1)	Source: 7F13081-01		Prepared & A	nalyzed: 06/15/17				
Total Suspended Solids	34.0	mg/l		33.0		3	20	
Duplicate (W7F0859-DUP2)	Source: 7F13081-02		Prepared & A	nalyzed: 06/15/17				
Total Suspended Solids	7.00	mg/l		7.00		0	20	
Batch: W7F1124 - SM 2520B								
Duplicate (W7F1124-DUP1)	Source: 7F13088-01		Prepared & A	nalyzed: 06/20/17				
Salinity	55.6	ppt		55.8		0.5	20	
Batch: W7F1189 - EPA 1664B								
Blank (W7F1189-BLK1)			Prepared & A	nalyzed: 06/21/17				
Oil & Grease (HEM)	1.3	mg/l		•				
LCS (W7F1189-BS1)			Prepared & A	nalyzed: 06/21/17				
Oil & Grease (HEM)	18.7	mg/l	20.0	94	78-114			
LCS (W7F1189-BS2)			Prepared & A	nalyzed: 06/21/17				
Oil & Grease (HEM)	4.20 1.3	mg/l	5.00	84	78-114			J



FINAL REPORT

IDE Americas, Inc. - Carlsbad CA

WECK LABORATORIES, INC.

Project Number: Carlsbad Desal Plant - WEEKLY

Reported:

06/30/2017 13:05

4590 Carlsbad Blvd Carlsbad, CA 92008

Project Manager: Peter Shen



Quality Control Results

(Continued)

Conventional Chemistry/Physical Parameters by APHA/	EPA/ASTI	M Methods (Continu	ed)							
				Spike	Source		%REC		RPD	
Analyte	Result	MDL	Units	Level	Result	%REC	Limits	RPD	Limit	Qualifier
Batch: W7F1189 - EPA 1664B (Continued)										
LCS Dup (W7F1189-BSD1)				Prepared & Ar	nalyzed: 06/2	1/17				
Oil & Grease (HEM)	- 18.6	1.3	mg/l	20.0		93	78-114	0.5	18	



Carlsbad, CA 92008

Certificate of Analysis

FINAL REPORT

IDE Americas, Inc. - Carlsbad CA 4590 Carlsbad Blvd

WECK LABORATORIES, INC.

Project Number: Carlsbad Desal Plant - WEEKLY

Reported: 06/30/2017 13:05

Project Manager: Peter Shen



Item

Notes and Definitions

J	Estimated conc. detected <mrl and="">MDL.</mrl>
ND	NOT DETECTED at or above the Method Reporting Limit (MRL). If Method Detection Limit (MDL) is reported, then ND means not detected at or above the MDL.
Dil	Dilution
dry	Sample results reported on a dry weight basis
RPD	Relative Percent Difference
% Rec	Percent Recovery
Source	Sample that was matrix spiked or duplicated.
MDL	Method Detection Limit
MRL	The minimum levels, concentrations, or quantities of a target variable (e.g., target analyte) that can be reported with a specified degree of confidence. The MRL is also known as Limit of Quantitation (LOQ) and Detection Limit for Reporting (DLR)
MDA	Minimum Detectable Activity
NR	Not Reportable
TIC	Tentatively Identified Compound (TIC) using mass spectrometry. The reported concentration is relative concentration based on the nearest internal

standard. If the library search produces no matches at, or above 85%, the compound is reported as unknown.

Any remaining sample(s) will be disposed of one month from the final report date unless other arrangements are made in advance.

An Absence of Total Coliform meets the drinking water standards as established by the California State Water Resources Control Board (SWRCB)

All results are expressed on wet weight basis unless otherwise specified.

All samples collected by Weck Laboratories have been sampled in accordance to laboratory SOP Number MIS 002.

7F13088 Page 8 of 8